

**Stormwater Management Wetlands Project**

**Estimate of Probable Cost for Planting**

**Exhibit 7**

Item	Quantity	Unit	Unit Price	Total
Wetland Plugs (10' buffer around open water, 12" o.c.)	71000	EA	\$ 4.00	\$284,000.00
Native Seed Mix 1 (10' buffer around open water)	1.63	AC	\$ 8,000.00	\$ 13,040.00
Native Seed Mix 1 (Wet Sedge Meadow)	6.35	AC	\$ 8,000.00	\$ 50,800.00
Native Seed Mix 2 (Upland Meadow, Low Profile Prairie)	3.31	AC	\$ 4,500.00	\$ 14,895.00
Native Tree Reforestation (1.5" cal., 25' o.c., 81 trees/ac.)	0	AC	\$12,150.00	\$ -
Live Stake Shrubs	1000	EA	\$ 20.00	\$ 20,000.00

**TOTAL \$382,735.00**